



Affordable Building
 Products of Florida
 11737 Broad Street
 Brooksville, FL 34601

Estimate

| E-mail | Date | Estimate # |
|---------------------------------|-----------|------------|
| info@affordablebuildingsllc.com | 10/6/2022 | 5026 |

Phone # 352-797-2108
 Web Site www.affordablebuildingsllc.com

| |
|--|
| Customer Information |
| City Of Dunnellon Troy Slattery 352-208-9021 20750 River Dr, Dunnellon, FL 34431 |
| Job Name |
| 20x15x10 OPB Perm |

| | | |
|-------------------------|---|------------|
| Project Location | modom@dunnellon.org | |
| | City Of Dunnellon Troy Slattery 352-208-9021 20750 River Dr, Dunnellon, FL 34431 45Mins 36Miles | |
| Barn Description | | Rep |
| 20x15x10 OPB Perm | | AM |

| Qty | Description |
|-----|---|
| | Install Open Pole Barn 20x15x10 29 ga PAINTED , 6x6x14 Posts. Concrete Slab: Existing 20x15 Slanted Slab ***Customer wants site check*** Engineered Drawings(Customer has Engineered Drawings from Driscoll). Permitting to be done by Customer. Lead time is 4- 6 weeks after permit approval. |
| 3 | 20' Gable Truss (2 sides Left and Right) 6x6 posts |
| 12 | Carriage Bolt Galvanized 1/2"-13x7" |
| 12 | 1/2" Galvanized Hex Nut |
| 9 | 1/2" Truss Connection Bolt, Zinc |
| 9 | 1/2" Truss Connection Nut, Zinc |
| 1 | Purlin Screws #9-15 X 1-1/2", 250/Bag |
| 2 | Painted #9-15 X 1-1/2" Woodgrip, 250/Bag COLOR: TBD |
| 36 | 2x6x10 Yellow Pine Boards |
| 4 | 2x6x12 Pressure Treated Boards |
| 6 | 6x6x14 Marine Grade Pressure Treated Post |
| 18 | 80# Bag Handi-Crete Concrete Mix |
| 150 | 29g Painted Ultra Rib Metal Roofing Panels COLOR: TBD |
| 2 | Ridge Cap 26g Painted COLOR: TBD |
| 800 | Labor provided for standard open span steel truss pole barns installation. |
| | Panel Info: Qty Ft. & In. Inches 12 - 12ft. 2in. = |

General Disclaimer

The given Estimate Price is only valid for 7 Days from the date of receipt.
 All credit card payments will incur a 3% Processing Fee.

Engineered drawings are NON-REFUNDABLE.

The height of all Pole Barn Eaves are from top of posts. Trusses are positioned 13" from the top of the post. Gable width is measured outside of post to outside of post. All gable trusses are 3:12 pitch & all lean to trusses are 1:12 pitch, unless modified otherwise. All Pole Barns have 18" overhang on all four sides, unless modified otherwise. All Pole Barns come with a 2X6 PT fascia board on gable ends, no metal trim. All purlins are 2X6 yellow pine, 24" on center. Unless stated in contract, Pole Barns are open air with no sides, trim or gables enclosed.

Upon receiving down payment, customer agrees to specs listed and becomes obligated to the stated total. Contract is not accepted until deposit is received. Final payment is due upon completion of project. All sales are final.



Affordable Building
 Products of Florida
 11737 Broad Street
 Brooksville, FL 34601

Estimate

| | | |
|---------------------------------|-----------|------------|
| E-mail | Date | Estimate # |
| info@affordablebuildingsllc.com | 10/6/2022 | 5026 |

Phone # Web Site
 352-797-2108 www.affordablebuildingsllc.com

| |
|--|
| Customer Information |
| City Of Dunnellon Troy Slattery 352-208-9021 20750 River Dr, Dunnellon, FL 34431 |
| Job Name |
| 20x15x10 OPB Perm |

| | | |
|---|---------------------|--|
| Project Location | modom@dunnellon.org | |
| City Of Dunnellon Troy Slattery 352-208-9021 20750 River Dr, Dunnellon, FL 34431 45Mins 36Miles | | |
| Barn Description | Rep | |
| 20x15x10 OPB Perm | AM | |

| Qty | Description |
|-----|--|
| 1 | Rebar 5/8"x20' #5 Grade 40 |
| 18 | 80# Bag Handi-Crete Concrete Mix |
| 1 | Lap Screws COLOR: TBD |
| 800 | Additional labor provided for permitted installation requirements. Additional materials and labor provided for permit required installations. |
| 1 | Permitting obtained by Customer / Does Not Include County Fees: TBD by your county (Please consider it could take between 6-8 weeks for county approval process) This timeline varies by municipality. |
| 1 | Mobilization Fee |
| | Valued Customer Discount- (2) Barn purchase & CFPB Victim |
| | Deposit upon acceptance.....\$ 628.33 (10%) |
| | Payment after barn completed.....\$ 4,654.92 |
| | After final inspection.....\$ 1,000.00 |

| | | |
|---------------------------|-------------------------|------------|
| General Disclaimer | Sales Tax (0.0%) | \$0.00 |
| | Total | \$6,283.25 |

The given Estimate Price is only valid for 7 Days from the date of receipt.
 All credit card payments will incur a 3% Processing Fee.

Engineered drawings are NON-REFUNDABLE.

The height of all Pole Barn Eaves are from top of posts. Trusses are positioned 13" from the top of the post. Gable width is measured outside of post to outside of post. All gable trusses are 3:12 pitch & all lean to trusses are 1:12 pitch, unless modified otherwise. All Pole Barns have 18" overhang on all four sides, unless modified otherwise. All Pole Barns come with a 2X6 PT fascia board on gable ends, no metal trim. All purlins are 2X6 yellow pine, 24" on center. Unless stated in contract, Pole Barns are open air with no sides, trim or gables enclosed.

Upon receiving down payment, customer agrees to specs listed and becomes obligated to the stated total. Contract is not accepted until deposit is received. Final payment is due upon completion of project. All sales are final.